

**CASH COUNTER EXTENSION & RENOVATION WORK OF  
AB BANK NICVD COLLECTION BOOTH.**

SL	DESCRIPTION OF WORK	UNIT	QNTY.	UNIT PRICE	AMOUNT (TK.)
01	<b>Dismantling Work:</b> Dismantling of existing brick wall (inner divider wall, counter side wall, main entry wall and others) and false ceiling (as instructed) carefully. These also include removal of the debris by the contractor to a suitable place. Precaution should be taken for the safety of other services (Electric, Machine, Hydraulic etc.) during dismantling removing & cleaning as per direction of AB Bank Ltd.	job	01		
02	<b>5" Brick wall:</b> Construction of 5" Brick wall by 1st class brick with cement mortar (1:4) in exterior, interior wall including cleaning, soaking the bricks at least 24 hours before use and washing the sand etc.; all complete as per design and instruction of the Engineer-in-charge.	sft	178		
03	<b>RCC work over door (Lintel):</b> Cement: sand: brick/stone chips (1:2:4) and placing the rebar as per design suggested by the authority/Engineer-in-charge.	rft	28		
04	<b>Plaster work:</b> Minimum ½" thick cement plaster (1:5) to wall, ceiling both inner and outer surfaces, finishing the corner and edges including washing of sand and curing at least for 7 days, all complete as per drawing and direction of the authority.	sft	381		
05	<b>Cash Counter:</b> New Supply, fitting & fixing of cash counter comprising of gorjon board sides and front support walls & melamine board inner work top with drawer unit, <b>18mm marble work in front, customer top and side wall</b> of the counter etc. all complete as per approved detail drawing and design including supply of all necessary materials and charges etc. Components: a. <b>18mm artificial marble</b> b. 25mm melamine board as working top c. New supply Drawer unit-05 nos.	rft	9		
06	<b>Collapsible gate:</b> Supply, fitting, fixing of collapsible gate made with 1"x1"x1½" MS angle and 1"x1" flat bar, all complete including enamel paint as per design and instruction of authority/Engineer in charge.	sft	40		
07	<b>Rolling Shutter:</b> Supply, fitting & fixing of rolling shutter made with 1mm thick imported Nickel / Zinc coated plain sheet, 3mm thick guide U channel. All complete as per direction of the authority/Engineer-in-charge.	sft	122		

08	<b>M.S grill work:</b> New supply fitting/fixing of M.S grill which made of (1/2"x1/2") square bar 4"c/c both way and 1 1/2"x1 1/2" MS box on horizontal and vertical in both way with interval distance inside of the curtain glass section with enamel paint finish, including all complete as per drawing and instruction of the authority/Engineer-in-charge	sft	45		
09	<b>Glass Partition with thai section:</b> 5 mm glass partition with frame over the cash counter including all accessories, all complete as per drawing and instruction of the authority/Engineer-in-charge.	sft	45		
10	<b>Tempered Glass door opening &amp; refitting:</b> Existing glass door opening & refitting/fixing of frameless glass door (size: 3'-0"x7'-0") made of 10mm thick tempered glass with all foreign made hardware/accessories such as stainless steel handles (24" long uniformly rounded), Concealed auto-closer, stopper, lock etc.; all complete as per design/drawing and instruction of the authority.	nos	2		
11	<b>Floor Tiles:</b> Supply & fitting/fixing of best quality Chinese homogeneous mirror polish tiles (size: 24"x24") with mortar (1:4) base maintaining proper sole/level and raking out the joints with matching color cement/pigment, curing at least 7 days; all complete as per drawing, design and instruction of the authority/Engineer in charge.	sft	85		
12	Drop ceiling over 8'-0" height glass partition	rft	35		
13	<b>Gypsum board Paneling:</b> Supply fitting fixing gypsum board paneling made of 12 mm gypsum board, <b>C-channel, U-channel</b> and screwed to RCC slab <b>including plastic paint</b> etc. all complete as per drawing/design & instruction of the authority/Engineer-in-charge.	sft	58		
14	<b>Gypsum board Partition:</b> Supply fitting fixing gypsum board partition made of 12 mm gypsum board, <b>C-channel, U-channel</b> and screwed to RCC slab <b>including plastic paint</b> etc. all complete as per drawing/design & instruction of the authority/Engineer-in-charge.	sft	45		
15	<b>Fixed ceiling:</b> Supplying, fitting/fixing false ceiling made of Gypsum Board suspended from RCC ceiling by 12SWG GI wire, screwed to RCC slab & <b>including plastic paint</b> etc. all complete as per drawing/design & instruction of the authority/Engineer-in-charge.	sft	58		

16	<b>Plastic paint (roller finish):</b> Plastic paint (Berger brand ) of approved color to/on plastered and others surfaces minimum 3 coats by roller finish after necessary lime putty work, cleaning, sand papering the base surfaces of wall treatment, including supply of all materials etc. all complete as per instruction of the authority/Engineer-in-charge.	sft	560		
17	<b>Enamel paint:</b> Enamel paint (Berger brand) of approved color minimum 3 coats by spray/brush finish after necessary putty work, cleaning, sand papering the surfaces, treatment, including supply of all materials etc. all complete in all respect as per instruction of the authority/Engineer-in-charge.	sft	210		
18	<b>Down light:</b> Supply, fitting & fixing of locally available 6” P. L. Down Light of approved color & size including conceal type shade of approved quality with all other necessary accessories etc. all complete up to testing & commissioning as per full satisfaction of the the authority i.e. ABBL.	nos	6		
19	<b>Panel Light:</b> Supply, fitting & fixing of- 2’ x 2’ locally available 48 watt surface Panel light ( <b>Brand: PASHA, Warranty-02 years</b> ) of approved color & size of approved quality with all other necessary accessories etc. all complete up to testing & commissioning as per full satisfaction of the authority i.e. AB Bank PLC.	nos	04		
20	<b>Ceiling Fan:</b> Supply, fitting/ fixing 56” ceiling Fan (Click/Walton or equivalent) with electrical connection etc. all complete as per drawing and direction of the authority/Engineer in-charge.	nos	04		
21	a) 3/4" dia PVC Pipe (with wall cutting and laying of pipe)	rft	50		
	b) 1" dia PVC Pipe (with wall cutting and laying of pipe)	rft	50		
	a) 13A, 3 pin socket	nos	04		
	a) 1C X 1.5 rm BYA cable	coil	02		
	b) 1C X 2.5 rm BYA cable	coil	01		
22	<b>SS Chain with stand for queue management work</b>	rft	142		
23	<b>Officer table refitting work with electric line connection work (Total 03 nos officer desk)</b>	job	01		

## **Terms & Conditions:**

1. **Currency:** Price must be quoted in Bangladeshi Taka (BDT).
2. **VAT and TAX:** Quoted price must be inclusive of VAT and TAX as per government rules. Bill will be paid after deducting VAT and TAX as per Govt. rules of Bangladesh.
3. **Validity of the offer:** The proposal shall remain open and valid for a period of at least 45 (Forty Five) days from the specified closing date indicated in the RFP for receipt of proposals. Your proposal should indicate that it will remain valid for this period. If your proposal is accepted during this period, the price quoted in your proposal must remain unchanged for the entire period of the resulting contract.
4. **Submission of offer:** Proposal/offer is to be submitted in sealed envelope which will be dropped in the Tender Box at level-2, AB Bank HO, The Skymark, 18 Gulshan Avenue, Gulshan-1, Dhaka-1212 **by 12:30 pm on February 18, 2025**. The following wordings: “**Schedule for cash counter extension and renovation work of AB Bank NICVD collection booth**” must be clearly written at the top of the envelope.
5. **Supervision:** Bank will supervise the interior fit-out work and will also check the quality and workmanship of the work. In the event of supply of any materials which do not match with the specified specifications or of substandard quality, the bank reserve the right for outright rejection of the goods and the supplier will have to take back and remove those at their own cost and will replace with acceptable quality materials within the shortest possible time from the date of rejection, without any extra cost or compensation.
6. **Workmanship Guarantee:** The Contractor is liable to a workmanship guarantee for a period of **six (06) months**. During this period of six months if any work done by the Contractor at his own cost. If not, the defective work will be done/repared though other agencies and the cost will be borne by the contractor.
7. **Authorized Signature on proposal:** Complete proposal/offer must be signed with date by the authorized representative of the company.
8. AB Bank PLC reserves the right to accept or rejection the proposal /offer without assigning any reasons thereof.
9. Manipulation or any kind of unusual approach or failure to submit the proposal/offer within stipulated time frame will be treated as “Disqualification” to participate in the bidding.
10. **Workmanship standards:** AB Bank PLC reserves the right to accept or reject any part of the work done by the contractor for poor workmanship or low standard of construction materials provided.
11. **Sample Approval:** AB Bank will approve materials prior to use/installation of any materials by the successful bidder at the premises.

12. **Quality of work:** Work to be completed with standard specification and high quality finishing.
13. **Additional work beyond scheduled work:** No additional work beyond the schedule is allowable unless written instruction from Bank. Bank will not entertain any such bills at the time of settlement of bill.
14. **Eligibility of submission:** Please submit the below mention document along with the schedule:
- a. Detail organization structure as per hierarchy including total number of technical / operational and administrative staffs
  - b. Up-to-date Trade License
  - c. TIN Certificate
  - d. VAT registration certificate
  - e. Up-to-date TAX payment receipt
  - f. Copy of work order with other organization
  - g. Experience certificate
  - h. Work completion certificate with other organization
  - i. Bank statement (Last 1 year) of the firm
  - j. Firm's balance sheet and statements of overall turnover
  - k. List of authorized persons of the company with copy of NID whom shall be contacted for subsequent correspondence by the Bank for issues after work order

If you fail to submit any of the required documents, your submission will be treat as rejected.

**All of you are requested to visit physically at AB Bank NICVD Collection Booth (Contact address: National Institute of Cardiovascular Diseases , Sher-e-Bangla Nagar, Dhaka-1207,) before submitting the quotation. Please contact with the Booth In-charge (Cell- 01928449897) should you have any queries or require any further information.**